LIGHT FIXTURE SCHEDULE												
TAG	DESCRIPTION	MANUFACTURER	MODEL	MOUNTING	FINISH	LUMENS	CRI	COLOR TEMPERATURE	WATTS	VOLTAGE	CONTROL TYPE	COMMENTS
A	TROFFER LIGHT 2'X4'	ELITE LIGHTING	24-FPL1-LED-4000/5000/6000L-DIM10-MVOLT-35K/45K/50K-85	RECESSED	COORDINATE WITH ARCHITECT	5310	80	4000K	41	UNV/120	0-10V 1%	
BG	STANDARD EMERGENCY LIGHTS	LITHONIA	EU2C	WALL AT 7.5' AFF	WHITE	N/A	N/A	N/A	1.8	120	N/A	
C	LOOP 48"	BETACALCO	RGTP1P04-LMA0880-CR90-CTA40	SURFACE/SUSPENDED	COORDINATE WITH ARCHITECT	8776	90	4000K	65	UNV/120	0-10V 1%	COORDINATE HEIGHT MOUNTING WITH ARCHITECT
C1	LOOP 60"	BETACALCO	RGTP1P05-LMA1100-CR90-CTA40	SURFACE/SUSPENDED	COORDINATE WITH ARCHITECT	10944	90	4000K	4.6/FT	120	0-10V 1%	REFER TO PLANS FOR LENGTH OF FIXTURES.
D4	DOWNLIGHT 4"	ELITE LIGHTING	HH4-LED-1000L/1500L/2000L/-DIM10-MVOLT-MD-27K/30K/35K/40K/50K-90-XX-XX	RECESSED	COORDINATE WITH ARCHITECT	2144	90	4000K	24	UNIV/120	0-10V 1%	
D6	DOWNLIGHT 6"	ELITE LIGHTING	HH6-LED-10HH6-LED-1000L/1500L/2000L/-DIM10-MVOLT-MD-27K/30K/35K/40K/50K-90-XX-XX0L/1500L/2000L/-DIM10-MVOLT-MD-27K/30K/35K/40K/50K-90-XX-XX	RECESSED	COORDINATE WITH ARCHITECT	1686	90	4000K				
D6W	DOWNLIGHT 6" WET	ELITE LIGHTING	HH6-6501-LED-1000L/1500L/2000L/-10DIM-MVOLT-M-27K/30K/35K/40K/50K-90-XX-XX									
F	LINEAR	ELITE LIGHTING	4-OC4-LED-4000L-DIM10-MVOLT-40K-85	SURFACE/SUSPENDED	COORDINATE WITH ARCHITECT	1332	85	4000K	30	UNIV/120	0-10V 1%	
J	LINEAR HIGH BAY	ELITE LIGHTING	CB2-CPA-LED-24000L/27000L/30000L-DIM10-MVOLT-WD-30K/35K/40K/50K-85	SURFACE/SUSPENDED	COORDINATE WITH ARCHITECT	25764		4000K				
V	VAPOR TIGHT FLOOD LIGHT	COOPER	VT0840L	WALL/CEILING	COORDINATE WITH ARCHITECT	875	N/A	4000K	184.2	213	0-10V 1%	
WP	WALL PACK	LITHONIA	TWX3-LED-ALO-40K-MVOLT-XX-XX-XX	WALL PACK	COORDINATE WITH ARCHITECT	13850	NA	4000K				
X	EXIT SIGN WITH EMERGENCY LIGHTS	EXIT LIGHT CO.	COMBOLG-G-B-BB-ST	WALL/CEILING AT A HEIGHT PER NFPA 101 REQUIREMENTS	GREEN LETTERS/BLACK HOUSING	N/A	N/A	N/A	9	120	N/A	REFER TO PLANS FOR ARROW SIGNAGE REQUIREMENTS ON EACH EXIT SIGN

Equipment Type	Manufacturer	Model	Width(In.)	Height(In.	Depth (In.	Weight (Lb.)
UPS	CE+T Power	Next Gen UPS-30kW	95.62	84.28	31.5	7000
SwitchBoard	Eaton	SCANFNNBF1B1B2	90	90	48	4000

alta
3510 N Main Avenue
San Antonio, Texas 78212
+1 (210) 349-1163
www.alta-architects.com

Permit/Seal

STATE OF TEXAS
ANDRES TAPIA CARRILLO
147602
LICENSED
PROFESSIONAL ENGINEER

Consultant

Verde Studio
ENGINEERING
TX Registration No. F-26247
3510 N Main Avenue
San Antonio, Texas 78212

DALLAS INDEPENDENT SCHOOL DISTRICT

DR. FREDERICK D. HAYNES III GLOBAL PREPARATORY ACADEMY AT PAUL QUINN COLLEGE

Client/Project
DALLAS INDEPENDENT SCHOOL DISTRICT

DR. FREDERICK D. HAYNES III
GLOBAL PREPARATORY ACADEMY
AT PAUL QUINN COLLEGE - UPPER CAMPUS
3837 SIMPSON STUART ROAD
DALLAS, TEXAS 75241

DATE 01/09/2026
PHASE BID ISSUE
PROJECT NO. E202422.00
DRAWN BY JEM
CHECKED BY ATC

ISSUE / REVISIONS

#	DESCRIPTION	DATE

BID ISSUE

Sheet Name
ELECTRICAL SCHEDULES

Drawing No.
E601

ORIGINAL SHEET - ARCH E1