VB — PANELBOARD SCHEDULE

LOCATION : FLAG FOOTBALL SCOREBOARD | **SCCR (AMPS RMS...** 35,000 | **SERVICE :** 208Y/120V 3Φ 4-Wire+Ground | **MAIN:** MCB
MOUNTING: SURFACE | **NEMA:** 3R | **AMP:** 225 A

CKT	DESCRIPTION	NOTE	AMP	POLE	A	B	C	POLE	AMP	NOTE	DESCRIPTION	CKT
1	DAKTRONICS PE1		80 A	2	8326 / 768			1	20 A		DAKTRONICS PS1	2
3						8326 / 180		1	20 A		NORTH PLAY CLOCK - FLAG FOOTBALL FIELD	4
5	DAKTRONICS PE2		80 A	2			8326 / 180	1	20 A		SOUTH PLAY CLOCK - FLAG FOOTBALL FIELD	6
7					8326 / 180			1	20 A		EAST FIELD POCKET - TRACK	8
9	DAKTRONICS PE3		80 A	2		8326 / 180		1	20 A		WEST FIELD POCKET - TRACK	10
11							8326 / 180	1	20 A		RECEPT	12
13	SPARE		80 A	2	0 / 180			1	20 A		SOUTH FIELD POCKET - LONG JUMP	14
15						0 / 180		1	20 A		NORTH FIELD POCKET - LONG JUMP	16
17	SPARE		80 A	2			0 / 540	1	20 A		RECEPTS - BLEACHER FACE - TRACK	18
19					0 / 0			1	20 A		SPARE	20
21	SPARE		80 A	2		0 / 0		1	20 A		SPARE	22
23							0 / 0	1	20 A		SPARE	24
25					0 / 0							26
27	SPARE		20 A	3		0 / 0		3	20 A		SURGE PROTECTION DEVICE	28
29							0 / 0					30
				TOTALS :	17779 VA	17191 VA	17551 VA					

TOTAL CONNECTED LOAD (VA) : 52522 VA **TOTAL CONNECTED LOAD (AMPS) :** 146 A
REMARKS:
NOTES:

1HDP — PANELBOARD SCHEDULE

LOCATION : ELEC. ROOM 122 | **SCCR (AMPS RMS...** 35,000 | **SERVICE :** 480Y/277V 3Φ 4-Wire+Ground | **MAIN:** MCB
MOUNTING: SURFACE | **NEMA:** 1 | **AMP:** 800 A

CKT	DESCRIPTION	NOTE	AMP	POLE	A	B	C	POLE	AMP	NOTE	DESCRIPTION	CKT
1					39960 / 0							2
3	TRANSFORMER (T-1) PANELBOARD '1LDP'		225 A	3		44544 / 0		3	225 A		SPARE	4
5							42475 / 0					6
7					43785 / 0							8
9	PANELBOARD '1SB1'		225 A	3		43785 / 0		3	225 A		SPARE	10
11							43785 / 0					12
13					29648 / 0							14
15	PANELBOARD '1TR1'		150 A	3		29648 / 0		3	100 A		SPARE	16
17							29648 / 0					18
19					27840 / 0							20
21	PANELBOARD '1H1'		150 A	3		26400 / 0		3	100 A		SPARE	22
23							25019 / 0					24
25					0 / 0							26
27	SPARE		400 A	3		0 / 0		3	60 A		SURGE PROTECTION DEVICE (SPD)	28
29							0 / 0					30
				TOTALS :	141232 VA	144376 VA	140926 VA					

TOTAL CONNECTED LOAD (VA) : 426534 VA **TOTAL CONNECTED LOAD (AMPS) :** 513 A
REMARKS:
NOTES:

1TR1 — PANELBOARD SCHEDULE

LOCATION : ELEC. ROOM 122 | **SCCR (AMPS RMS...** 35,000 | **SERVICE :** 480Y/277V 3Φ 4-Wire+Ground | **MAIN:** MCB
MOUNTING: SURFACE | **NEMA:** 1 | **AMP:** 150 A

CKT	DESCRIPTION	NOTE	AMP	POLE	A	B	C	POLE	AMP	NOTE	DESCRIPTION	CKT
1					5792 / 665							2
3	SOUTHWEST POLE TRACK AND FIELD 'F1'		30 A	3		5792 / 665		3	30 A		BLEACHER LIGHTING - POLES 'F1' & 'F2' TRACK AND FIELD	4
5							5792 / 665					6
7					5792 / 0							8
9	NORTHWEST POLE TRACK AND FIELD 'F2'		30 A	3		5792 / 0		3	30 A		SPARE	10
11							5792 / 0					12
13					2712 / 0							14
15	NORTHEAST POLE TRACK AND FIELD 'F3'		30 A	3		2712 / 0		3	30 A		SPARE	16
17							2712 / 0					18
19					3252 / 0							20
21	CENTER EAST POLE TRACK AND FIELD 'F5'		30 A	3		3252 / 0		3	50 A		SPARE	22
23							3252 / 0					24
25					4238 / 7197							26
27	SOUTHEAST POLE TRACK AND FIELD 'F4'		30 A	3		4238 / 7197		3	50 A		TRACK AND FIELD - PRESSBOX	28
29							4238 / 7197					30
31					0 / 0							32
33	SPARE		30 A	3		0 / 0		3	30 A		SURGE PROTECTION DEVICE (SPD)	34
35							0 / 0					36
				TOTALS :	29648 VA	29648 VA	29648 VA					

TOTAL CONNECTED LOAD (VA) : 88943 VA **TOTAL CONNECTED LOAD (AMPS) :** 107 A
REMARKS:
NOTES:

1S1 — PANELBOARD SCHEDULE

LOCATION : | **SCCR (AMPS RMS...** 22,000 | **SERVICE :** 208Y/120V 3Φ 4-Wire+Ground | **MAIN:** MCB
MOUNTING: SURFACE | **NEMA:** 3R | **AMP:** 100 A

CKT	DESCRIPTION	NOTE	AMP	POLE	A	B	C	POLE	AMP	NOTE	DESCRIPTION	CKT
1	SPARE		20 A	1	0 / 0			1	20 A		SPARE	2
3	SPARE		20 A	1		0 / 0		1	20 A		SPARE	4
5	SPARE		20 A	1			0 / 0	1	20 A		SPARE	6
7	3RD BASE DUGOUT/STORAGE - NORTH FIELD		20 A	1	840 / 840			1	20 A		3RD BASE DUGOUT/STORAGE - SOUTH FIELD	8
9	3RD BASE CAMERA WELL - NORTH FIELD		20 A	1		500 / 180		1	20 A		3RD BASE CAMERA WELL - SOUTH FIELD	10
11	3RD BASE BULLPEN RECEPT - NORTH FIELD		20 A	1			180 / 180	1	20 A		3RD BASE BULLPEN RECEPT - SOUTH FIELD	12
13	SCOREBOARD - NORTH FIELD		20 A	1	1340 / 720			1	20 A		BATTING CAGES - SOUTH FIELD	14
15	SCOREBOARD RECEPT - NORTH FIELD		20 A	1		180 / 1340		1	20 A		SCOREBOARD - SOUTH FIELD	16
17	BATTING CAGES - NORTH FIELD		20 A	1			1200 / 180	1	20 A		SCOREBOARD RECEPT - SOUTH FIELD	18
19	1ST BASE BULLPEN RECEPT - NORTH FIELD		20 A	1	180 / 180			1	20 A		1ST BASE BULLPEN RECEPT - SOUTH FIELD	20
21	1ST BASE DUGOUT/STORAGE - NORTH FIELD		20 A	1		840 / 180		1	20 A		1ST BASE CAMERA WELL - SOUTH FIELD	22
23	1ST BASE CAMERA WELL - NORTH FIELD		20 A	1			360 / 816	1	20 A		1ST BASE DUGOUT - SOUTH FIELD	24
25	BACKSTOP RECEPT - NORTH FIELD		20 A	1	180 / 180			1	20 A		BACKSTOP RECEPT - SOUTH FIELD	26
27	RECEPTS - SHOTPUT & DISCUS BLEACHERS		20 A	1		360 / 0		1	20 A		SPARE	28
29	NORTHWEST FLOOR POCKET - SHOTPUT &...		20 A	1			180 / 0	1	20 A		SPARE	30
31	NORTHWEST FLOOR POCKET - SHOTPUT &...		20 A	1	360 / 0			1	20 A		SPARE	32
33	EAST FLOOR POCKETS - SHOTPUT & DISCUS		20 A	1		360 / 0		1	20 A		SPARE	34
35	SPARE		20 A	1			0 / 0	1	20 A		SPARE	36
37	SPARE		20 A	1	0 / 0							38
39	SPARE		20 A	1		0 / 0		3	20 A		SURGE PROTECTION DEVICE	40
41	SPARE		20 A	1			0 / 0					42
				TOTALS :	4820 VA	3940 VA	3096 VA					

TOTAL CONNECTED LOAD (VA) : 11856 VA **TOTAL CONNECTED LOAD (AMPS) :** 33 A
REMARKS:
NOTES:

1SB1 — PANELBOARD SCHEDULE

LOCATION : ELEC. ROOM 122 | **SCCR (AMPS RMS...** 35,000 | **SERVICE :** 480Y/277V 3Φ 4-Wire+Ground | **MAIN:** MCB
MOUNTING: SURFACE | **NEMA:** 1 | **AMP:** 225 A

CKT	DESCRIPTION	NOTE	AMP	POLE	A	B	C	POLE	AMP	NOTE	DESCRIPTION	CKT
1					2332 / 0							2
3	BLEACHER LIGHTING NORTH/SOUTH SOFTBALL FIELDS		30 A	3		2332 / 0		3	30 A		SPARE	4
5							2332 / 0					6
7					6275 / 4637							8
9	3RD BASE/LEFTFIELD POLES 'A1', 'B1', 'C1' NORTH SOFTBALL FIELD		30 A	3		6275 / 4637		3	30 A		3RD BASE/LEFT FIELD POLES 'A3', 'B3', 'C3' SOUTH SOFTBALL FIELD	10
11							6275 / 4637					12
13					4501 / 4064							14
15	1ST BASE/RIGHT FIELD POLES 'A2', 'B2', 'C2' NORTH SOFTBALL FIELD		30 A	3		4501 / 4064		3	30 A		1ST BASE/RIGHT FIELD POLES 'A4', 'B4', 'C4' SOUTH SOFTBALL FIELD	16
17							4501 / 4064					18
19					2169 / 7197							20
21	OUTFIELD POLES 'C3' & 'C2' - DISCUS & SHOTPUT SOFTBALL FIELDS		30 A	3		2169 / 7197		3	50 A		SOFTBALL PRESSBOX PANELBOARD NORTH SOFTBALL FIELD	22
23							2169 / 7197					24
25					5413 / 7197							26
27	DISCUS/SHOTPUT POLES - 'P1', 'P2', 'P3' NORTH SOFTBALL FIELD		30 A	3		5413 / 7197		3	50 A		SOFTBALL PRESSBOX PANELBOARD SOUTH SOFTBALL FIELD	28
29							5413 / 7197					30
31					0 / 0							32
33	SPARE		30 A	3		0 / 0		3	50 A		SPARE	34
35							0 / 0					36
37					0 / 0							38
39	SPARE		30 A	3		0 / 0		3	30 A		SURGE PROTECTION DEVICE (SPD)	40
41							0 / 0					42
				TOTALS :	43785 VA	43785 VA	43785 VA					

TOTAL CONNECTED LOAD (VA) : 131355 VA **TOTAL CONNECTED LOAD (AMPS) :** 158 A
REMARKS:
NOTES:

INTERIOR LIGHT FIXTURE SCHEDULE

MARK	DESCRIPTION	MOUNTING	WATTS	CRI	COLOR	LUMENS	VOLTS	MANUFACTURER(S)	MARK
F01.12	LINEAR 4-INCH WIDE BY 12-FOOT LONG, WHITE DIFFUSER, 0-10V DIMMING TO 10-PERCENT.	RECESSED	85 W	80	4000K	725/FT	120-277V	LITECONTROL 4L-R-D SERIES STARTEK RBEAM SERIES MARK SLOT 4 SERIES	F01.12
F20	1 BY 4-FOOT LENSED TROFFER, WHITE FLUSH STEEL DOOR, 0.125-INCH PATTERN 12 ACRYLIC LENS, 0-10V DIMMING TO 10-PERCENT, NON-IC RATED.	RECESSED IN ACT GRID	51 W	80	4000K	4755	120-277V	COLUMBIA LJT14 SERIES LITHONIA GTL SERIES METALUX 14GRLED SERIES	F20
F20G	1 BY 4-FOOT LENSED TROFFER, WHITE FLUSH STEEL DOOR, 0.125-INCH PATTERN 12 ACRYLIC LENS, 0-10V DIMMING TO 10-PERCENT, NON-IC RATED.	RECESSED IN GYP	51 W	80	4000K	4755	120-277V	COLUMBIA LJT14 SERIES LITHONIA GTL SERIES METALUX 14GRLED SERIES	F20G
F25	2 BY 4-FOOT ARCHITECTURAL TROFFER, ANGLED DOOR, DIFFUSE CENTER OPTIC, 0-10V DIMMING TO 10-PERCENT, NON-IC RATED.	RECESSED	41 W	80	4000K	5416	120-277V	COLUMBIA LCAT24 SERIES LITHONIA BLTBA SERIES VISCOR LRTH SERIES	F25
F32	OPEN DOWNLIGHT, 6-INCH DIAMETER APERTURE, CLEAR SEMI-SPECULAR REFLECTOR, SELF FLANGED, 0-10V DIMMING TO 10-PERCENT, NON-IC RATED.	RECESSED	15 W	80	4000K	1100	120-277V	HALO COMMERCIAL HC6 SERIES LITHONIA LDN6 SERIES PRESCOLITE LC6 SERIES	F32
F60	4-FOOT LENSED INDUSTRIAL, FORMED STEEL HOUSING, WHITE FINISH, SEMI-FROST ACRYLIC DIFFUSER.	SURFACE/ CHAIN HUNG	48 W	80	4000K	5000	120-277V	COLUMBIA MPS SERIES LITHONIA ZL1D SERIES METALUX SNLED SERIES	F60
F70	2-FOOT NOMINAL UNDERCOUNTER LIGHT, WHITE DIFFUSER, MULTI-VOLT, ON/OFF ROCKER SWITCH, ANTI-MICROBIAL FINISH.	SURFACE	12 W	80	4000K	1200	120-277V	ACUITY HUC SERIES AIREY-THOMPSON 13L SERIES FAIL-SAFE UCL SERIES	F70
F81	6-INCH SURFACE DOWNLIGHT, 80 CRI, WET LOCATION LISTED, WHITE FINISH.	SURFACE	16 W	80	4000K	1032	120-277V	PRESCOLITE LBSE-6RD SERIES HALO SMX6 SERIES JUNO JSF-7IN SERIES	F81
FL	LED STRIP WITH SELF-ADHESIVE AND SCREW MOUNTING CLIPS, IP65 RATED EXTRUSION EXTRUSION, DIFFUSED LENS, 0-10V DIMMING TO 10-PERCENT, PROVIDE REMOTE LED POWER SUPPLIES AS REQUIRED, PROVIDE END CAPS AS REQUIRED, ARCHITECT TO SELECT EXTRUSION FINISH FROM CATALOG OF STANDARD FINISHES, MOUNT LIGHT FIXTURE TO UNDERSIDE OF PREFABRICATED CANOPY, PROVIDE MOUNTING FASTENERS AND ACCESSORIES AS REQUIRED.	SURFACE	447 W	70	5000K	288/FT	120-277V	TAPE: KLUS WP-K-50-1910-HD-IP65-24V SERIES BEULUX VIENNA LED SERIES QTRAN SW24/3.0 SERIES EXTRUSION: KLUS PDS4-ALU SERIES BEULUX AA02 SERIES QTRAN TORQ SERIES	FL
FN	ARCHITECTURAL WALL PACK, FULL-CUTOFF, WET LOCATION LISTED, BLACK FINISH.	SURFACE WALL	40 W	70	5000K	5400	120-277V	ENERGY HARNESS EHF-WPR-40 SERIES NO EQUALS	FN
X1	CAST ALUMINUM EXIT SIGN, BRUSHED FACE, BLACK HOUSING, SELF POWERED, SELF DIAGNOSTIC.	UNIVERSAL	5 W	80	RED	N/A	120-277V	DUAL-LITE SE SERIES SURE-LITES CX SERIES LITHONIA LE SERIES	X1
X4	EMERGENCY LIGHTING UNIT, 90-MINUTE EMERGENCY CAPACITY, DAMP LOCATION LISTED, SELF DIAGNOSTIC.	SURFACE WALL	5 W	80	WHITE	N/A	120-277V	DUAL-LITE EV SERIES SURE-LITES SEL25 SERIES LITHONIA ELM2 SERIES	X4

1L1 — PANELBOARD SCHEDULE

LOCATION : ELEC. ROOM 122 | **SCCR (AMPS RMS...** 22,000 | **SERVICE :** 208Y/120V 3Φ 4-Wire+Ground | **MAIN:** MLO
MOUNTING: SURFACE | **NEMA:** 1 | **AMP:** 225 A

CKT	DESCRIPTION	NOTE	AMP	POLE	A	B	C	POLE	AMP	NOTE	DESCRIPTION	CKT
43	SPARE		20 A	1	0 / 0			1	20 A		SPARE	44
45	SPARE		20 A	1		0 / 0		1	20 A		SPARE	46
47	SPARE		20 A	1			0 / 0	1	20 A		SPARE	48
49	QUAD RECEPTS - COACHES OFFICE 112		20 A	1	720 / 360			1	20 A		NW RECEPTS - EQUIP. STOR. TRACK 119	50
51	GEN RECEPTS - COACHES OFFICE 112		20 A	1		360 / 540		1	20 A		NE RECEPTS - EQUIP. STOR. TRACK 119	52
53	RECEPT - TOILET 113		20 A	1			180 / 360	1	20 A		E. RECEPTS - EQUIP. STOR. TRACK 119	54
55	GEN RECEPTS - LOCKER ROOM 115		20 A	1	540 / 360			1	20 A		SE RECEPTS - EQUIP. STOR. TRACK 119	56
57	EWC, RESTROOM RECEPTS - LOCKER ROOM 115		20 A	1		540 / 360		1	20 A		S. RECEPTS - EQUIP. STOR. TRACK 119	58
59	QUAD RECEPT - LOCKER ROOM 115		20 A	1			360 / 360	1	20 A		NW RECEPTS - EQUIP. STOR. TRACK 119	60
61	RECEPT - STORAGE 114		20 A	1	180 / 360			1	20 A		NW RECEPTS - EQUIP. STOR. TRACK 119	62
63	S. RECEPTS - EQUIP. STOR. SOFTBALL 120		20 A	1		540 / 180		1	20 A		NW RECEPTS - EQUIP. STOR. TRACK 119	64
65	E. RECEPTS - EQUIP. STOR. SOFTBALL 120		20 A	1			360 / 720	1	20 A		OVERHEAD DOOR - EQUIPMENT STOR. TRACK...	66
67	N. RECEPTS - EQUIP. STOR. SOFTBALL 120		20 A	1	360 / 888			1	20 A		UNIT HEATERS - EQUIP. STOR. TRACK 119	68
69	W. RECEPTS - EQUIP. STOR. SOFTBALL 120		20 A	1		540 / 1000		1	20 A		WALL HEATER - GROUNDS OFFICE 105	70
71	OVERHEAD DOOR - EQUIP. STOR. SOFTBALL 120		20 A	1			720 / 1000	1	20 A		WALL HEATER - LOCKER ROOM 115	72
73	UNIT HEATERS - EQUIP. STOR. SOFTBALL 120		20 A	1	444 / 750			1	20 A		ELECTRIC BASEBOARD (EBBR) - TOILET 113	74
75	ROOFTOP RECEPT - CONDENSING UNIT ACCU-A		20 A	1		180 / 1000		1	20 A		FIRE ALARM CONTROL PANEL - ELEC. ROOM 122	76
77	ROOFTOP RECEPT - RTU		20 A	1			360 / 0	1	20 A		SPARE	78
79	RECEPTS - ELEC. ROOM 123		20 A	1	540 / 0							80
81	ACCU-A/DS-A (ROOF) SERVES ELECTRICAL ROOM		25 A	2		1768 / 0		3	20 A		SURGE PROTECTION DEVICE (SPD)	82
83							1768 / 0					84
				TOTALS :	5502 VA	7008 VA	6188 VA					

TOTAL CONNECTED LOAD (VA) : 18698 VA **TOTAL CONNECTED LOAD (AMPS) :** 52 A
REMARKS:
FED VIA FEED THRU LUGS IN SECTION 1.
NOTES:

1L1 — PANELBOARD SCHEDULE

LOCATION : ELEC. ROOM 122 | **SCCR (AMPS RMS...** 22,000 | **SERVICE :** 208Y/120V 3Φ 4-Wire+Ground | **MAIN:** MCB
MOUNTING: SURFACE | **NEMA:** 1 | **AMP:** 225 A

CKT	DESCRIPTION	NOTE	AMP	POLE	A	B	C	POLE	AMP	NOTE	DESCRIPTION	CKT
1	SPARE		20 A	1	0 / 0			1	20 A		SPARE	2
3	SPARE		20 A	1		0 / 0		1	20 A		SPARE	4
5	SPARE		20 A	1			0 / 0	1	20 A		SPARE	6
7	RECEPT - RESTROOM 117		20 A	1	180 / 360			1	20 A		SOUTH RECEPT - CORRIDOR 121	8
9	RECEPTS (TRAINING BED) - TRAINER 118		20 A	1		360 / 180		1	20 A		SOUTH CENTER RECEPT - CORRIDOR 121	10
11	RECEPTS (TRAINING BED) - TRAINER 118		20 A	1			360 / 180	1	20 A		CENTER RECEPT - CORRIDOR 121	12
13	GEN RECEPTS - TRAINER 118		20 A	1	360 / 180			1	20 A		NORTH CENTER RECEPT - CORRIDOR 121	14
15	REFRIGERATOR - TRAINER 118		20 A	1		180 / 360		1	20 A		NORTH RECEPT - CORRIDOR 121	16
17	COUNTERTOP RECEPT #1 - TRAINER 118		20 A	1			180 / 540	1	20 A		RECEPTS - WOMENS 102, MENS 104, FAMILY 103	18
19	COUNTERTOP RECEPT #2 - TRAINER 118		20 A	1	180 / 1000			1	20 A		ELECTRIC HEATER (EUH-B) - FAMILY R.R. 103	20
21	ICE MAKER TRAINER 118		20 A	2		1375 / 720		1	20 A		QUAD RECEPTS - GROUNDS OFFICE 105	22
23							1375 / 540	1	20 A		GEN. RECEPTS - GROUNDS OFFICE 105	24
25	ICE MAKER RECEPT - TRAINER 118		20 A	1	180 / 360			1	20 A		RECEPT - RESTROOM 106	26
27	ELECTRIC HEATER (EUH-B) - TRAINER 118		20 A	1		1000 / 900		1	20 A		QUAD RECEPTS - COACHES OFFICE 107	28
29	EXHAUST FAN (EF-B) - TRAINER 118		20 A	1			840 / 540	1	20 A		GEN. RECEPTS - COACHES OFFICE 107	30
31	EXHAUST FAN (EF-C) - SOFTBALL STORAGE 120		20 A	1	1727 / 0			1	20 A		TRACK/FIELD LIGHTING CONTACTOR	32
33	MOTORIZED DAMPERS - RIV-A, RIV-B - STORAGE		20 A	1		250 / 0		1	20 A		TRACK/FIELD AUXILIARY LIGHTING INTERFACE...	34
35	MOTORIZED DAMPERS (WEST) - RIV-A - ABOVE...		20 A	1			125 / 0	1	20 A		SOFTBALL LIGHTING CONTACTOR	36
37					936 / 0			1	20 A		SOFTBALL AUXILIARY LIGHTING INTERFACE...	38
39	EXHAUST FAN (EF-D) - ROOF STORAGE TRACK 119		20 A	3		936 / 0		1	20 A		SPARE	40
41							936 / 0	1	20 A		SPARE	42
				TOTALS :	10965 VA	13269 VA	11804 VA					

TOTAL CONNECTED LOAD (VA) : 36037 VA **TOTAL CONNECTED LOAD (AMPS) :** 100 A
REMARKS:
FEED-THRU LUGS TO SECTION 2.
NOTES:

1L2 — PANELBOARD SCHEDULE

LOCATION : MECH. 111 | **SCCR (AMPS RMS...** 22,000 | **SERVICE :** 208Y/120V 3Φ 4-Wire+Ground | **MAIN:** MLO
MOUNTING: SURFACE | **NEMA:** 1 | **AMP:** 200 A

CKT	DESCRIPTION	NOTE	AMP	POLE	A	B	C	POLE	AMP	NOTE	DESCRIPTION	CKT
1	SPARE		20 A	1	0 / 0			1	20 A		SPARE	2
3	SPARE		20 A	1		0 / 0		1	20 A		SPARE	4
5	SPARE		20 A	1			0 / 0	1	20 A		SPARE	6
7	ROOFTOP MAINTENANCE OUTLET - ACCU-A		20 A	1	180 / 720			1	20 A		GEN. RECEPTS - MECHANICAL 111	8
9	ELECTRIC UNIT HEATER (EUH-B) - CUSTODIAN...		20 A	1		1000 / 180		1	20 A		WATER SOFTENER - MECHANICAL 111	10
11	GEN. RECEPTS - CUSTODIAN 101		20 A	1			720 / 180	1	20 A		THERMOSTATIC MIXING VALVE (TMV-A) - MECH....	12
13	NORTHWEST QUAD RECEPT - VENDING 100		20 A	1	360 / 600			1	20 A		WATER HEATER (WH-A) - MECHANICAL 111	14
15	WEST COUNTERTOP RECEPT - VENDING 100		20 A	1		180 / 500		1	20 A		TEMPERATURE CONTROL PANEL - MECH. 111	16
17	WEST COUNTERTOP RECEPT - VENDING 100		20 A	1			180 / 864	1	20 A		CIRCULATION PUMP (CP-A) - MECHANICAL 111	18
19	SOUTH COUNTERTOP RECEPT - VENDING 100		20 A	1	180 / 180			1	20 A		ENTRANCE GATES - SOFTBALL COMPLEX	20
21	SOUTH COUNTERTOP RECEPT - VENDING 100		20 A	1		180 / 180		1	20 A		ENTRANCE GATES - SOFTBALL COMPLEX	22
23	EAST COUNTER RECEPT - VENDING 100		20 A	1			180 / 180	1	20 A		LIGHTED SIGN - CANOPY	24
25	EAST COUNTER RECEPT - VENDING 100		20 A	1	180 / 180			1	20 A		FUTURE LIGHTING - ENTRANCE CANOPY	26
27	EAST COUNTER RECEPT - VENDING 100		20 A	1		180 / 180		1	20 A		REFRIGERATOR - VENDING 100	28
29	EAST COUNTER RECEPT - VENDING 100		20 A	1			180 / 1000	1	20 A		IRRIGATION CONTROLLER - MECH. 111	30
31	EAST COUNTER RECEPT - VENDING 100		20 A	1	180 / 0			1	20 A		SPARE	32
33	EAST QUAD RECEPT - VENDING 100		20 A	1		360 / 0		1	20 A		SPARE	34
35	NORTHEAST QUAD RECEPT - VENDING 100		20 A	1			360 / 0	1	20 A		SPARE	36
37	NORTHWEST QUAD RECEPT - VENDING 100		20 A	1	360 / 0			1	20 A		SPARE	38
39	SOUTHWEST TV MONITOR - VENDING 100		20 A	1		180 / 1040		2	20 A		IRRIGATION PUMP - MECH. 111	40
41	EAST TV MONITOR - VENDING 100		20 A	1			360 / 1040					42
43	SPARE		20 A	1	0 / 4820							44
45	CONDENSING UNIT (ACCU-A) VENDING/		25 A	2		1768 / 3940		3	100 A		PANEL '1S1' (NORTH SOFTBALL FIELD)	46
47							1768 / 3096					48
49					576 / 0							50
51	EXHAUST FAN (EF-A) CUST. 101		20 A	3		576 / 0		3	20 A		SURGE PROTECTION DEVICE (SPD)	52
53							576 / 0					54
				TOTALS :	8516 VA	10444 VA	10684 VA					

TOTAL CONNECTED LOAD (VA) : 29643 VA **TOTAL CONNECTED LOAD (AMPS) :** 82 A
REMARKS:
NOTES:

1L3 — PANELBOARD SCHEDULE

LOCATION : STORAGE 110 | **SCCR (AMPS RMS...** 22,000 | **SERVICE :** 208Y/120V 3Φ 4-Wire+Ground | **MAIN:** MLO
MOUNTING: SURFACE | **NEMA:** 1 | **AMP:** 125 A

CKT	DESCRIPTION	NOTE	AMP	POLE	A	B	C	POLE	AMP	NOTE	DESCRIPTION	CKT
1	SPARE		20 A	1	0 / 0			1	20 A		SPARE	2
3	SPARE		20 A	1		0 / 0		1	20 A		SPARE	4
5	SPARE		20 A	1			0 / 0	1	20 A		SPARE	6
7	RECEPTS - STORAGE 110		20 A	1	540 / 180			1	20 A		COUNTERTOP RECEPT - TEAM ROOM 108	8
9	RACK RECEPT #1 - TECH. 109		20 A	1		360 / 180		1	20 A		COUNTERTOP RECEPT - TEAM ROOM 108	10
11	RACK RECEPT #2 - TECH. 109		20 A	1			360 / 180	1	20 A		COUNTERTOP RECEPT - TEAM ROOM 108	12
13	GEN. QUAD RECEPTS - TECH. 109		20 A	1	720 / 180			1	20 A		COUNTERTOP RECEPT - TEAM ROOM 108	14
15	DOOR CONTROLLER - TECH. 109		20 A	1		1000 / 1200		1	20 A		TEAM ROOM 108	16
17	EXHAUST FAN (EF-C) - TECH. 109		20 A	1			696 / 180	1	20 A		COUNTERTOP RECEPT - TEAM ROOM 108	18
19	WEST QUAD RECEPT - TEAM ROOM 108		20 A	1	180 / 180			1	20 A		COUNTERTOP RECEPT - TEAM ROOM 108	20
21	WEST QUAD RECEPT - TEAM ROOM 108		20 A	1		180 / 180		1	20 A		COUNTERTOP RECEPT - TEAM ROOM 108	22
23	WEST QUAD RECEPT - TEAM ROOM 108		20 A	1			180 / 480	1	20 A		REFRIGERATOR - TEAM ROOM 108	24
25	TV MONITOR - TEAM ROOM 108		20 A	1	360 / 0			1	20 A		SPARE	26
27	WEST QUAD RECEPT - TEAM ROOM 108		20 A	1		180 / 0		1	20 A		SPARE	28
29	SOUTH QUAD RECEPT - TEAM ROOM 108		20 A	1			180 / 0	2	20 A		SPARE	30
31	SOUTH QUAD RECEPT - TEAM ROOM 108		20 A	1	180 / 0							32
33	SOUTH QUAD RECEPT - TEAM ROOM 108		20 A	1		180 / 0		2	30 A		SPARE	34
35	SOUTH QUAD RECEPT - TEAM ROOM 108		20 A	1			180 / 0					36
37	NORTHWEST QUAD - TEAM ROOM 108		20 A	1	180 / 0							38
39	NORTHEAST QUAD - TEAM ROOM 108		20 A	1		180 / 0		3	20 A		SURGE PROTECTION DEVICE (SPD)	40
41	SPARE		20 A	1			0 / 0					42
				TOTALS :	2700 VA	3640 VA	2436 VA					

TOTAL CONNECTED LOAD (VA) : 8776 VA **TOTAL CONNECTED LOAD (AMPS) :** 24 A
REMARKS:
NOTES:

1LDP — PANELBOARD SCHEDULE

LOCATION : ELEC. ROOM 122 | **SCCR (AMPS RMS...** 22,000 | **SERVICE :** 208Y/120V 3Φ 4-Wire+Ground | **MAIN:** MCB
MOUNTING: SURFACE | **NEMA:** 1 | **AMP:** 500 A

CKT	DESCRIPTION	NOTE	AMP	POLE	A	B	C	POLE	AMP	NOTE	DESCRIPTION	CKT
1					10965 / 17779							2
3	PANELBOARD '1L1'		225 A	3		13269 / 17191		3	225 A		PANELBOARD 'VB'	4
5							11804 / 17551					6
7					8516 / 2700							8
9	PANELBOARD '1L2'		225 A	3		10444 / 3640		3	125 A		PANELBOARD '1L3'	10
11							10684 / 2436					12
13	PROVISION		--	1	0 / 0			1	--		PROVISION	14
15	PROVISION		--	1		0 / 0		1	--		PROVISION	16
17	PROVISION		--	1			0 / 0	1	--		PROVISION	18
19	PROVISION		--	1	0 / 0			1	--		PROVISION	20
21	PROVISION		--	1		0 / 0		1	--		PROVISION	22
23	PROVISION		--	1			0 / 0	1	--		PROVISION	24
25	PROVISION		--	1	0 / 0			1	--		PROVISION	26
27	PROVISION		--	1		0 / 0		1	--		PROVISION	28
29	PROVISION		--	1			0 / 0	1	--		PROVISION	30
31	PROVISION		--	1	0 / 0							32
33	PROVISION		--	1		0 / 0		3	60 A		SURGE PROTECTION DEVICE (SPD)	34
35	PROVISION		--	1			0 / 0					36
				TOTALS :	39960 VA	44544 VA	42475 VA					

TOTAL CONNECTED LOAD (VA) : 126978 VA **TOTAL CONNECTED LOAD (AMPS) :** 352 A
REMARKS:
NOTES:

1H1 — PANELBOARD SCHEDULE

LOCATION : ELEC. ROOM 122 | **SCCR (AMPS RMS...** 35,000 | **SERVICE :** 480Y/277V 3Φ 4-Wire+Ground | **MAIN:** MLO
MOUNTING: SURFACE | **NEMA:** 1 | **AMP:** 150 A

CKT	DESCRIPTION	NOTE	AMP	POLE	A	B	C	POLE	AMP	NOTE	DESCRIPTION	CKT
1	SPARE		20 A	1	0 / 0			1	20 A		SPARE	2
3	SPARE		20 A	1		0 / 0		1	20 A		SPARE	4
5	SPARE		20 A	1			0 / 0	1	20 A		SPARE	6
7	NORTH PARKING LOT LIGHTING		20 A	1	2100 / 1040			1	20 A		LIGHTING - WOMENS 102, FAMILY RR 103, MEN...	8
9	CENTRAL PARKING LOT LIGHTING		20 A	1		1650 / 533		1	20 A		LIGHTING - VEND. 100, CUST. 101, MECH. 111	10
11	SOUTH PARKING LOT LIGHTING		20 A	1			1650 / 380	1	20 A		LIGHTING - OFFICE 105, COACH OFFICE 107, RR...	12
13	FLAGPOLE LIGHTING		20 A	1	120 / 1647			1	20 A		LIGHTING - STORAGE 119, SOFTBALL STOR. 120	14
15	EXTERIOR BUILDING MOUNTED LIGHTING		20 A	1		807 / 1081		1	20 A		LIGHTING - OFFICE 112, RR 113, STOR. 114,...	16
17	SPARE		20 A	1			0 / 857	1	20 A		LIGHTING - TEAM 108, STOR. 110, TECH 109	18
19	SPARE		20 A	1	0 / 801			1	20 A		LIGHTING - CORRIDOR 121, TRAINER 118, RR 117	20
21	SPARE		20 A	1		0 / 197		1	20 A		LIGHTING - ELECTRICAL ROOM 122	22
23	SPARE		20 A	1			0 / 0	1	20 A		SPARE	24
25					3333 / 1667							26
27	ELECTRIC UNIT HEATER (EUH-A) WOMENS 102, MENS 104		20 A	3		3333 / 1667		3	20 A		ELECTRIC PROPELLER UNIT HEATER MOTOR MECH. 111	28
29							3333 / 1667					30
31					3333 / 6233							32
33	ELECTRIC UNIT HEATERS CORRIDOR 121		20 A	3		3333 / 6233		3	30 A		ROOFTOP UNIT (RTU-A)	34
35							3333 / 6233					36
37					1333 / 6233							38
39	ELECTRIC UNIT HEATER (EUH-A) VENDING 100		20 A	3		1333 / 6233		3	30 A		ROOFTOP UNIT (RTU-A)	40
41							1333 / 6233					42
				TOTALS :	27840 VA	26400 VA	25019 VA					

TOTAL CONNECTED LOAD (VA) : 79259 VA **TOTAL CONNECTED LOAD (AMPS) :** 95 A
REMARKS:
NOTES:

Brownsburg Community School Corporation
Higher Achievement • Together

CSO
8831 Keystone Crossing, Indianapolis, IN 46240
317.848.7800 | csoinc.net
© 2018 CSO Architects, Inc. All Rights Reserved

DA#24095
R.E. Dimond
Consulting Engineers
732 North Capitol Ave.
Indianapolis, IN 46204
P: (317) 634-4672 F: (317) 638-8725 www.redimond.com

PROJECT:
BROWNSBURG COMMUNITY SCHOOL CORPORATION
BROWNSBURG HIGH SCHOOL
SOFTBALL & TRACK
1000 S ODELL ST, BROWNSBURG, IN 46112

SCOPE DRAWINGS:
These drawings indicate the general scope of the project in terms of architectural design concept, the dimensions of the building, the major architectural elements and the type of structural, mechanical and electrical systems.
The drawings do not necessarily indicate or describe all work required for full performance and completion of the requirements of the Contract.
On the basis of the general scope indicated or described, the trade contractors shall furnish all items required for the proper execution and completion of the work.

REVISIONS:

ISSUE DATE	DRAWN BY	CHECKED BY
01/09/2026	JPS	JPS

DRAWING TITLE:
LIGHTING & PANELBOARD SCHEDULES - ELECTRICAL

CERTIFIED BY:
JOSEPH PAUL SIOTA
REGISTERED
No. 12200363
STATE OF
INDIANA
PROFESSIONAL ENGINEER
Joseph Paul Siota
1/9/26

DRAWING NUMBER
E-601

PROJECT NUMBER
2024038